

CUSTOM HOME TIMELINE

TYPICAL ENGAGEMENT · 16 TO 18 MONTHS

1 · DUE DILIGENCE PHASE · ABOUT 1 WEEK

- Gather home comparables for project guidance
- Order survey if missing; confirm zoning, setbacks, floodplain, tree survey (Austin heritage tree rules apply at 24 inches)

2 · HIRING PHASE · 1 TO 2 WEEKS

Interviews conducted in order: architect, builder, designer (if applicable), landscape architect (if applicable). Decision on the build team is finalized before the design phase begins.

3 · DESIGN PHASE · 1 TO 3 MONTHS, ITERATIVE PLAN DEVELOPMENT

- Initial team meeting and introductions
- 1:1 with builder on budget building; 1:1 with architect on wishlist and initial plans; 1:1 with designer on initial finishes and mood board
- Design meeting 2: plans review, corrections, budget alignment, sizing
- Second pass of plans with designer on call; Walk Your Plans for finishes, layout, and functionality
- Design finishes meeting: major selections and budget
- Third pass: exterior finishes, ceiling heights, flow; additional passes as needed
- Final plan set and mood board finalized with major selections penciled in

4 · PRE-CONSTRUCTION · WEEKS PRECEDING GROUNDBREAKING

- Demo permit pulled if applicable
- Plans submitted to the city; building permits pulled

5 · CONSTRUCTION · ABOUT 12 MONTHS, BROAD-SCOPE MILESTONES

1. Site prep: cleared, utilities marked
2. Foundation: excavation, footings, slab or foundation walls, waterproofing, backfill, first major inspection
3. Framing and dry-in: walls, floor systems, roof, windows and exterior doors; weather-tight shell
4. MEP rough-ins and inspections; fireplaces set

Throughout the project · ongoing touchpoints

DESIGNER CHECK-INS · BI-WEEKLY DURING CONSTRUCTION

Designer walks the site with VFV and the builder to confirm finish placement, verify material staging, and resolve field questions before they become change orders.

MONTHLY BUDGET REVIEWS · FIRST WEEK OF EACH MONTH

A single sit-down each month covering draw activity to date, projected spend for the coming 30 days, variance against contracted allowances, and any recommended reallocations.

UPCOMING SELECTION MEETINGS · SCHEDULED 4 TO 6 WEEKS AHEAD

Selections are calendared before they are needed on site: plumbing, lighting, appliances, cabinetry hardware, tile, and specialty items, so lead times never delay the build.

SUBCONTRACTOR QUOTE REVIEWS · AS BIDS COME IN

Every subcontractor quote is checked against industry-standard pricing for materials and labor. When a bid is out of line, VFV presents alternative subcontractor options.

OUR COMMITMENT

All communication with your architect, designer, builder, and tradespeople funnels through VFV: one point of contact from day one through Certificate of Occupancy, so your interests are

5. Insulation, drywall, and interior finishes begin: trim, doors, stairs, cabinetry staged
6. Cabinetry, fixtures, flooring, and landscape: countertops, tile, hardwood, paint, appliances, hardscape
7. Punch list, C.O., and move-in: final inspections, walkthroughs, keys delivered

protected and decisions are made with full information.